

---

CONSTRUCTION SPECIFICATION  
CS-OR-008 MOBILIZATION AND DEMOBILIZATION

---

008.1 SCOPE

The work consists of the mobilization and demobilization of the contractor's forces and equipment necessary for performing the work required as well as any work required to remove excess materials and equipment from the work site once the project is complete.

008.2 EQUIPMENT AND MATERIAL

Mobilization shall include all activities involved in the transportation of contractor's personnel, equipment, and operating supplies to the site; establishment of offices, buildings, and other necessary general facilities for the contractor's operations at the site; any permits, insurance, and/or bonds required to do the work; and other items specified in Section 008.3 of this specification.

Demobilization shall include all activities involved in the transportation of personnel, equipment, and supplies not required or included in the contract from the site; including the disassembly, removal, and site cleanup of offices, buildings, and other facilities assembled on the site specifically for this contract.

008.3 ITEMS OF WORK AND CONSTRUCTION DETAILS