



Description: RECTANGULAR TANK W/ CONCRETE TOP AND GREATER THAN 3 FT. EXTENDED ABOVE GROUND


DRAWN BY: WATSON STATE DESIGN TEAM  
 Filename: OH051500.DWG

REPRODUCED WITH PERMISSION FROM:  
 Concrete Manure Storages Handbook,  
 MWPS-36  
 1st EDITION, 1994  
 © MIDWEST PLAN SERVICE  
 AMES, IA 50011-3080

- NOTES:
- 1- CONCRETE COMPRESSIVE STRENGTH,  $f'_c$ , SHALL BE 4,000 PSI.
  - 2- REINFORCING STEEL SHALL BE GRADE 60.
  - 3- CONCRETE COVER OVER REINFORCING STEEL SHALL BE 2" CLEAR. WHEN FORMED AGAINST EARTH, COVER SHALL BE 3" CLEAR.
  - 4- FOR ADDITIONAL DETAILS, SEE SHEET \_\_\_.



**DETAIL A**



- \* DOWELS (DEFORMED REINFORCING STEEL)**
- OPTION 1: EXTEND 12" OF VERTICAL STEEL INTO FOOTING.  
 EXTEND STEEL VERTICALLY INTO THE FOOTING WITHIN 3" OF FOOTING BOTTOM, THEN BEND 90°.
- OPTION 2: USE A 24" LONG BAR, EQUIVALENT TO THE VERTICAL STEEL.  
 TIE 12" OF THE DOWEL TO THE VERTICAL STEEL.  
 EXTEND VERTICALLY INTO THE FOOTING WITHIN 3" OF FOOTING BOTTOM, THEN BEND 90°.

**FLOOR THICKNESS AND STEEL:**  
 THE FLOOR SLAB THICKNESS AND REINFORCING STEEL REQUIREMENTS SHALL BE AS SPECIFIED IN THE NRCS-OHIO CONSTRUCTION SPECIFICATION "CONCRETE".

NOT TO SCALE

STANDARD DRAWING NO.: OH-N-515-CAD  
 APPROVAL DATE: 7/25/00

REVISIONS:

Date	
Designed	
Drawn	
Checked	
Approved	

RECTANGULAR TANK WITH CONCRETE TOP  
 AND  
 GREATER THAN 3 FEET EXTENDED ABOVE GROUND



File No. oh051500.dwg
Drawing No.
Sheet of